




PROJECT SUMMARY

This project consisted of full abatement and demolition of 3 floors which spanned approximately 20,000 Sqft each and the complete removal and disposal of 20,000 Sqft of roofing materials. The roofing materials included gravel, multiple felt layers and 12" thick light weight concrete. The demolition and offload were a challenge on this project due to the campus and library remaining open to students and faculty. A negative airflow was constructed to offload roof debris and asbestos waste directly from the roof into 40 yard dumpsters.

DIVISIONS

- > Demolition
- > Environmental

UC Berkeley Moffitt Library

 UC Berkeley

Full indoor abatement and demolition with complete roof removal and disposal.

CLIENT/OWNER

University California Berkeley

GENERAL CONTRACTOR



DURATION

8 Months

COMPLETION DATE

May 2016

CONTRACT VALUE

\$1,244,116

PROJECT SIZE

80,000 Sqft.

CREW SIZE

20-25

* Project Code: 15244